





NOTES :-

1. सभी माप मिलीमीटर में तथा ऊंचाई मीटर में दिए गए हैं।  
ALL DIMENSIONS ARE IN MILLIMETERS AND LEVELS IN METERS.
2. THE DEFINITION OF 'A' & 'B' LINE AND VARIOUS CLASSES OF EXCAVATION SHOWN SHALL BE AS PER SECTION B.3 OF TECHNICAL SPECIFICATION.
3. MINOR MODIFICATION IN THE LENGTH, ORIENTATION, PATTERN AND LOCATION OF ROCK ANCHORS MAY BE DONE TO SUIT THE SITE CONDITIONS WITH THE APPROVAL OF ENGINEER-IN-CHARGE.
4. UNLESS CLASS-VB IS ENCOUNTERED THE STEEL RIBS SHOWN IN THE DRAWING SHALL BE AS PROPOSED FOR CLASS-VA IRRESPECTIVE OF THE ROCK CLASS, STEEL RIB SHALL BE CONFORMING TO SECTION B.4 OF TECHNICAL SPECIFICATION. SPACING OF STEEL RIBS SHOWN MAY BE MODIFIED TO SUIT THE SITE CONDITIONS WITH THE APPROVAL OF ENGINEER-IN-CHARGE.
5. ROCK ANCHORS SHOWN IN THE DRAWING SHALL BE CONFORMING TO SECTION B.4 OF TECHNICAL SPECIFICATION.
6. REQUIREMENT OF 45 MM DIA. 5000 LONG (INTO ROCK) PRESSURE RELIEF HOLES WITH 36 MM DIA. PERFORATED PVC PIPES AS PER SECTION B.7 OF TECHNICAL SPECIFICATION WILL BE DETERMINED BY ENGINEER-IN-CHARGE TO SUIT THE SITE CONDITION.
7. SHOTCRETE SHOWN ON DRAWING SHALL BE APPLIED AS SPECIFIED IN SECTION B.5 OF TECHNICAL SPECIFICATION.
8. STEEL LAGGING OR PRE CAST CONCRETE LAGGING AS SPECIFIED IN SECTION B.4 OF TECHNICAL SPECIFICATIONS SHALL BE USED IN CLASS VA WITH THE APPROVAL OF ENGINEER-IN-CHARGE.
9. ADDITIONAL MEASURES FOR TUNNELING IN POOR REACHES (WHERE RMR VALUE OF ROCK IS LESS THAN 35) SHALL BE ADOPTED AS PER DRG. NO. NHDB-4BC4-41-DD-1007 AS DIRECTED BY ENGINEER-IN-CHARGE.
10. UNDERGROUND EXCAVATION INCLUDING PROTECTION OF TUNNEL INVERT SHALL BE CONFIRMING TO SECTION B.3 OF TECHNICAL SPECIFICATION.
11. FOR ADIT TO MIV FLOOR ROCK SUPPORT OUTSIDE THE LIMITS SHOWN, REFER DRG. NO. NHDB-4BC4-41-DD-1024.
12. M25/A40 GRADE FOR INVERT CONCRETE AND M15/A40 FOR BACKFILL CONCRETE CONFORMING TO SECTION B.9 OF TECHNICAL SPECIFICATION SHALL BE USED.
13. FOR CONCRETE & REINFORCEMENT IN AHU PLATFORM REFER SEPARATE DRAWING.

**REFERENCE DRAWINGS:-**

1. NHDB-4BC4-41-DD-0002.
2. NHDB-4BC4-41-DD-1007.
3. NHDB-4BC4-41-DD-1024 & 1026.

**SCALE:**



13.02.2025		00		ISSUED FOR CONSTRUCTION											
DATE	NO	REVISION OR ISSUES			BY	CH. APP.	DRAWN डॉक्टर DEEPAK	SUBMITTED प्रस्तुत PRABHAT ASHWAL	RECOMMENDED अनुशंसा RAJEEV KUMAR			DEM / HM		APPROVED अनुमोदित CH. AUTH.	
DESIGN MEMO NO. मेमो नं. 1000							DATE दिनांक	FEB 2025	DRG. NO. ड्रॉइंग नं.	NHDB		4BC4	41	DD	1037 00