







1. सभी माप मिलीमीटर में दिए गए हैं।
ALL DIMENSIONS ARE IN MILLIMETERS.
2. ARRAY OF MPBX AND SPBX ALONG WITH LOAD CELLS AS SHOWN IN THE DRAWING SHALL BE INSTALLED AS PER MANUFACTURER'S INSTRUCTION MANUAL AND AS SPECIFIED IN TECHNICAL SPECIFICATION B.18.
3. MPBX (3POINTS) AND SPBX ARRAY TO BE INSTALLED IMMEDIATELY BEHIND ADVANCE FACE AS AND WHERE DIRECTED BY ENGINEER-IN-CHARGE.
4. NUMBER AND LOCATION OF INSTRUMENTS SHALL BE FINALISED BY THE ENGINEER-IN-CHARGE AS PER SITE CONDITIONS.
5. ALL INSTRUMENTS SHALL BE PROPERLY CALIBRATED AND CERTIFIED BEFORE INSTALLING AT THE LOCATIONS.
6. THE DAILY READING OF THE INSTRUMENTS SHALL BE OBSERVED DURING CONSTRUCTION AND DATA BE ANALYSED AND SUBMITTED TO THE ENGINEER-IN-CHARGE. FREQUENCY OF READINGS MAY BE DECREASED BY ENGINEER-IN-CHARGE ON ACHIEVING STABLE READINGS.
7. NECESSARY PRECAUTIONS SHALL BE TAKEN DURING AND AFTER TUNNEL EXCAVATION TO ENSURE THAT INSTALLED INSTRUMENTS DO NOT GET DAMAGED.
8. THE INSTRUMENTS DAMAGED DURING CONSTRUCTION SHALL BE REPLACED IMMEDIATELY.



0 1.0 2.0 3.0 4.0 5.0 METRE

<p>एन एच पी सी लिमिटेड (भारत सरकार का उद्यम) NHPC Limited (A GOVT. OF INDIA ENTERPRISE)</p>				
<p>दिबांग बहुउद्देशीय परियोजना DIBANG MULTIPURPOSE PROJECT</p>				
<p>POWER HOUSE COMPLEX ADITS/GALLERIES/BUS DUCTS INSTRUMENTATION SCHEME TYPICAL DETAILS</p>				
<p>DRAWN अंकित</p>	<p>SUBMITTED संशोधित</p>	<p>RECOMMENDED अनुमोदित</p>	<p>APPROVED अनुमोदित & प्रमाणित</p>	
<p>APF</p>	<p>REPAK</p>	<p>प्रमुख प्रशासक आसाम अनुमोदित RABEE KUMAR</p>	<p>DEM / HM</p>	
<p>DATE दिनांक</p>	<p>JUL 2024</p>	<p>DRG. NO. ड्राइंग संख्या</p>	<p>NHDB</p>	<p>4AC4 41 DD 1002</p>